

Automotive IPD 2ch Low Side Switch

BM2LC120FJ-C

Features

- AEC-Q100 Qualified^(Note 1)
- Built-in Over Current Protection Function(OCP)
- Built-in Thermal Shutdown Function (TSD)
- Built-in Active Clamp Function
- Built-in Diagnostic Function
- Direct Control Enabled from CMOS Logic IC, etc.
- On Resistance R_{DS(ON)} = 120 mΩ(Typ) (when V_{IN} = 5 V, I_{OUT} = 0.8 A, Tj = 25 °C)
- Monolithic Power Management IC with the Control Block (CMOS) and Power MOS FET Mounted on a Single Chip

(Note 1) Grade1

General	Descri	ntion
Ochici ai	Descii	Puvii

The BM2LC120FJ-C is an automotive 2ch low side switch IC, which has built-in OCP, TSD, active clamp function.

Also, diagnostic function can diagnose OCP, TSD, open load detection function (OLD).

Key Specifications

On-state Resistance (Tj = 25 °C, Typ)	120 mΩ	
Over Current Detection Current	6 A	
(Tj = 25 °C, Typ)	0 A	
Output Clamp Voltage (Min)	42 V	
Active Clamp Energy (Tj(START) = 25 °C)	140 mJ	

Package SOP-J8

W (Typ) x D (Typ) x H (Max) 4.90mm x 6.00mm x 1.65mm



Application

Driving Resistive, Inductive and Capacitive Load

Block Diagram(Note 1)




Figure 1. Block Diagram

(Note 1) There are two blocks in this product.

Contents

Features	1
General Description	1
Application	1
Key Specifications	1
Package	1
Block Diagram	1
Contents	2
Pin Configuration	
Pin Description	3
Term	
Absolute Maximum Ratings	4
Recommended Operating Conditions	
Thermal Resistance	
Electrical Characteristics	9
Typical Performance Curves	11
Measurement Circuit for Typical Performance Curves	18
I/O Pin Truth Table	20
Timing Chart	20
Function Description	22
Operational Notes	24
Ordering Information	25
Marking Diagram	
Physical Dimension and Packing Information	26
Revision History	27

Pin Configuration




Figure 2. Pin Configuration

Pin Description

Pin No.	Pin Name ^(Note 1)	Function
1	IN1	Input pin 1, with internal pull-down resistor.
2	ST1	Self-diagnostic output pin 1.
. 3	IN2	Input pin 2, with internal pull-down resistor.
4	ST2	Self-diagnostic output pin 2.
5	GND2	GND pin 2.
6	OUT2	Output pin 2, when output pin shorted to battery and output current exceeding the over current detection value, output current will be limited to protect IC.
7	GND1	GND pin 1.
8	OUT1	Output pin 1. When output pin shorted to battery and output current exceeding the over current detection value, output current will be limited to protect IC.

(Note 1) The number in Pin Name is the channel number.

Term




Figure 3. Term

Absolute Maximum Ratings(Tj = 25°C)

Parameter	Symbol	Ratings	Unit
Output Voltage	Vouт	-0.3 to +42	V
Input Voltage	VIN	-0.3 to +7	V
Output Current	lout(ocp)	3.0 (inside limited) ^(Note 1)	Α
Diagnostic Output Voltage	Vst	-0.3 to +7	V
Diagnostic Output Current	Ist	10	mA
Active Clamp Energy (Single Pulse) Tj(START) = 25 °C(Note 2)	E _{AS(25 °C)}	140	m. l
Active Clamp Energy (Single Pulse) Tj(START) = 150 °C(Note 2) (Note 3)	EAS(150 °C)	50	mJ
Operating Temperature Range	Tj	-40 to +150	°C
Storage Temperature Range	Tstg	-55 to +150	°C
Maximum Junction Temperature	Tjmax	150	°C

Caution 1: Operating the IC over the absolute maximum ratings may damage the IC. The damage can either be a short circuit between pins or an open circuit between pins and the internal circuitry. Therefore, it is important to consider circuit protection measures, such as adding a fuse, in case the IC is operated over the absolute maximum ratings.

Caution 2: Should by any chance the maximum junction temperature rating be exceeded the rise in temperature of the chip may result in deterioration of the properties of the chip. In case of exceeding this absolute maximum rating, design a PCB boards with thermal resistance taken into consideration by increasing board size and copper area so as not to exceed the maximum junction temperature rating.

(Note 1) Internally limited by over current protection function.

(Note 2) Active clamp energy (Single Pulse), at the condition $I_{OUT(START)} = 1.9 \text{ A}$, $V_{BAT} = 16 \text{ V}$.

$$E_{AS} = \frac{1}{2} LI_{OUT(START)}^{2} \times (1 - \frac{V_{BAT}}{V_{BAT} - V_{OUT(CL)}})$$

(Note 3) Not 100 % tested.

Recommended Operating Conditions

Parameter	Symbol Min		Тур	Max	Unit
Input Voltage	VIN	3.0	5.0	5.5	V
Operating Temperature	Tj	-40	+25	+150	°C

Thermal Resistance(Note 1)

Parameter	Symbol	Тур	Unit	Condition	
SOP-J8 (1ch ON)					
		167.9	°C/W	1s (Note 2)	
Between Junction and Surroundings Temperature Thermal Resistance	θ_{JA}	105.8	°C/W	2s (Note 3)	
		85.6	°C/W	2s2p (Note 4)	

Parameter	Symbol	Тур	Unit	Condition	
SOP-J8 (All ch ON)	·				
		141.5	°C/W	1s (Note	
Between Junction and Surroundings Temperature Thermal Resistance	θја	84.1	°C/W	2s (Note	
		67.1	°C/W	2s2p (Note	

(Note 1) The thermal impedance is based on JESD51-2A (Still-Air) standard. It is used the chip of BM2LC120FJ-C

(Note 2) JESD51-3 standard FR4 114.3 mm x 76.2 mm x 1.57 mm 1-layer (1s)

(Top copper foil: ROHM recommended Footprint + wiring to measure, 2 oz. copper.) (Note 3)JESD51-5 standard FR4 114.3 mm x 76.2 mm x 1.60 mm 2-layers (2s)

(Top copper foil: ROHM recommended Footprint + wiring to measure/ Copper foil area on the reverse side of PCB: 74.2 mm x 74.2 mm,

copper (top & reverse side) 2 oz.)

(Note 4) JESD51-5/-7 standard FR4 114.3 mm x 76.2 mm x 1.60 mm 4-layers (2s2p)

(Top copper foil: ROHM recommended Footprint + wiring to measure/

2 inner layers and copper foil area on the reverse side of PCB: 74.2 mm x 74.2 mm,

copper (top & reverse side/inner layers) 2 oz./1 oz.)

PCB Layout 1 layer (1s)




Figure 4. PCB Layout 1 layer (1s)

Dimension	Value		
Board Finish Thickness	1.57 mm ± 10 %		
Board Dimension	76.2 mm x 114.3 mm		
Board Material	FR4		
Copper Thickness (Top Layer)	0.070 mm (Cu:2 oz)		

Thermal Resistance - continued

■ PCB Layout 2 layers (2s)





Figure 5. PCB Layout 2 layers (2s)

Dimension	Value		
Board Finish Thickness	1.60 mm ± 10 %		
Board Dimension	76.2 mm x 114.3 mm		
Board Material	FR4		
Copper Thickness (Top/Bottom Layers)	0.070 mm (Cu + Plating)		

Thermal Resistance - continued

■ PCB Layout 4 layers (2s2p)





Cross Section

Figure 6. PCB Layout 4 layers (2s2p)

Dimension	Value		
Board Finish Thickness	1.60 mm ± 10 %		
Board Dimension	76.2 mm x 114.3 mm		
Board Material	FR4		
Copper Thickness (Top/Bottom Layers)	0.070 mm (Cu + Plating)		
Copper Thickness (Inner Layers)	0.035 mm		

Thermal Resistance - continued

■ Transient Thermal Resistance (Single Pulse) 1ch ON




Figure 7. Transient Thermal Resistance

■ Transient Thermal Resistance (Single Pulse) All ch ON




Figure 8. Transient Thermal Resistance

Electrical Characteristics (Unless otherwise specified, -40 °C ≤ Tj ≤ +150 °C)

Doromotor	Cuma ha a l		Limit		1110:4	Conditions
Parameter	Symbol	Min	Тур	Max	Unit	Conditions
Output Clamp Voltage	V _{OUT(CL)}	42	48	54	V	V _{IN} = 0 V,I _{OUT} = 1 mA
On-state Resistance (V _{IN} = 5 V, Tj = 25 °C)	R _{DS(ON)}	-	120	160	mΩ	V _{IN} = 5 V,I _{OUT} = 0.8 A,Tj = 25 °C
On-state Resistance (V _{IN} = 5 V, Tj = 150 °C)	R _{DS(ON)}	-	230	300	mΩ	V _{IN} = 5 V,I _{OUT} = 0.8 A,Tj = 150 °C
On-state Resistance (V _{IN} = 3 V, Tj = 25 °C)	R _{DS(ON)}	-	160	230	mΩ	V _{IN} = 3 V,I _{OUT} = 0.8 A,Tj = 25 °C
On-state Resistance ($V_{IN} = 3 \text{ V, Tj} = 150 \text{ °C}$)	R _{DS(ON)}	-	290	420	mΩ	V _{IN} = 3 V,I _{OUT} = 0.8 A,Tj = 150 °C
Leak Current (Tj = 25 °C)	I _{OUT(L)}	40	60	80	μA	V _{IN} = 0 V,V _{OUT} = 18 V,Tj = 25 °C
Leak Current (Tj = 150 °C)	I _{OUT(L)}	50	85	200	μΑ	V _{IN} = 0 V,V _{OUT} = 18 V,Tj = 150 °C
Turn-ON TIME	ton	-	-	60	μs	$V_{IN} = 0 \text{ V to 5 V, } R_L = 15 \Omega,$ $V_{BAT} = 12 \text{ V, } Tj = 25 \text{ °C}$
Turn-OFF TIME	toff	-	-	60	μs	$V_{IN} = 5 \text{ V to 0 V}, R_L = 15 \Omega, V_{BAT} = 12 \text{ V}, Tj = 25 °C$
Slew Rate On	SRON	-	1.3	2.5	V/µs	$V_{IN} = 0 \text{ V to 5 V, } R_{L} = 15 \Omega,$ $V_{BAT} = 12 \text{ V, } Tj = 25 \text{ °C}$
Slew Rate Off	SR _{OFF}	-	1.5	2.7	V/µs	$V_{IN} = 5 \text{ V to 0 V}, R_{L} = 15 \Omega,$ $V_{BAT} = 12 \text{ V}, Tj = 25 \text{ °C}$
Input Threshold Voltage	V _{IN(TH)}	1.5	-	2.7	V	R _L = 15 Ω, V _{BAT} = 12 V
High-level Input Current1 (in Normal Operation)	I _{IN(H1)}	-	125	250	μA	V _{IN} = 5 V
High-level Input Current2 (in Abnormal Operation)(Note 1)	I _{IN(H2)}	-	-	500	μA	V _{IN} = 5 V
Low-level Input Current	I _{IN(L)}	-10	0	+10	μA	V _{IN} = 0 V
Over Current Detection Current	I _{OUT(OCP)}	3	6	9	А	V _{IN} = 5 V, V _{BAT} = 12 V, Tj = 25 °C
Thermal Shutdown Operated Temperature ^(Note 2)	Tjo	150	175	-	°C	V _{IN} = 5 V
Thermal Shutdown Released Temperature ^(Note 2)	Tjr	135	-	-	°C	V _{IN} = 5 V
Thermal Shutdown Hysteresis	Тјднүѕ	-	15	-	°C	V _{IN} = 5 V

(Note 1) When thermal shutdown function or over current protection function is ON. (Note 2) Not 100 % tested.

Electrical Characteristics (Unless otherwise specified, -40 °C ≤ Tj ≤ +150 °C) - continued

Parameter	Symbol	Limit		Unit	Conditions	
Farameter		Min	Тур	Max	Offic	Conditions
Open Load Detection Voltage	VOPEN	1.5	-	4.5	V	V _{IN} = 0 V
ST Output On Voltage1	V _{ST(ON1)}	-	0.2	0.5	V	V _{IN} = 5 V, I _{ST} = 1 mA
ST Output On Voltage2	V _{ST(ON2)}	-	0.2	0.5	V	$\begin{split} V_{\text{IN}} &= 0 \text{ V, } V_{\text{OUT}} = 4.5 \text{ V,} \\ I_{\text{ST}} &= 0.5 \text{ mA} \end{split}$
ST Output Leak Current1	I _{ST(L1)}	-	-	20	μA	V _{IN} = 5 V, V _{ST} = 5 V
ST Output Leak Current2	I _{ST(L2)}	-	-	20	μA	$V_{IN} = 0 \text{ V}, V_{OUT} = 1.5 \text{ V}, V_{ST} = 5 \text{ V}$
ST Output Delay Time Detect	tSTDET	-	1	30	μs	$\begin{aligned} V_{\text{IN}} &= 0 \text{ V, } V_{\text{OUT}} = 5 \text{ V to 1 V,} \\ V_{\text{MCU}} &= 5 \text{ V, } R_{\text{ST}} = 10 \text{ k}\Omega, \ C_{\text{ST}} = 10 \text{ pF} \end{aligned}$
ST Output Delay Time Release	tstrel	-	1	30	μs	$\begin{aligned} V_{\text{IN}} &= 0 \text{ V}, V_{\text{OUT}} = 1 \text{ V to 5 V}, \\ V_{\text{MCU}} &= 5 \text{ V}, R_{\text{ST}} = 10 \text{ k}\Omega, C_{\text{ST}} = 10 \text{ pF} \end{aligned}$




Figure 9. Output Clamp Voltage vs Junction Temperature

Figure 10. On-state Resistance vs Input Voltage




Figure 11. On-state Resistance vs Junction Temperature

Figure 12. Leak Current vs Junction Temperature




Figure 13. Turn-ON TIME vs Input Voltage

Figure 14. Turn-OFF TIME vs Input Voltage




Figure 15. Turn-ON TIME vs Junction Temperature

Figure 16. Turn-OFF TIME vs Junction Temperature




Figure 17. Slew Rate On vs Input Voltage

Figure 18. Slew Rate Off vs Input Voltage




Figure 19. Slew Rate On vs Junction Temperature

Figure 20. Slew Rate off vs Junction Temperature




Figure 21. Input Threshold Voltage vs Junction Temperature

Figure 22. High-level Input Current1 (In Normal Operation) vs Input Voltage




Figure 23. High-level Input Current1 (in Normal Operation) vs Junction Temperature




Figure 24. Over Current Detection Current vs Output Voltage




Figure 25. Over Current Detection Current vs Junction Temperature

Figure 26. Open Load Detection Voltage vs Junction Temperature




Figure 27. ST Output On Voltage1 vs Junction Temperature

Figure 28. ST Output On Voltage2 vs Junction Temperature




Figure 29. ST Output Leak Current1 vs Junction Temperature

Figure 30. ST Output Leak Current2 vs Junction Temperature




Figure 31. ST Output Delay Time Detect vs Junction Temperature

Figure 32. ST Output Delay Time Release vs Junction Temperature






Figure 33. Active Clamp Energy (Single Pulse) vs Output Current (Start)


Measurement Circuit for Typical Performance Curves




Measurement Circuit for Figure 9




Measurement Circuit for Figure 10, 11




Measurement Circuit for Figure 12




Measurement Circuit for Figure 13, 14, 15, 16, 17, 18, 19, 20




Measurement Circuit for Figure 21



Measurement Circuit for Figure 22, 23




Measurement Circuit for Figure 24, 25




Measurement Circuit for Figure 26


Measurement Circuit for Typical Performance Curves - continued




Measurement Circuit for Figure 27




Measurement Circuit for Figure 28



Measurement Circuit for Figure 29



Measurement Circuit for Figure 30



Measurement Circuit for Figure 31, 32

I/O Pin Truth Table

Output Function

Input Signal	Operating Status	Output Status	
L	Standby	OFF	
Н	Normal	ON	
Н	Over Current	Current Limiting	
Н	Over Temperature	OFF	

Diagnostic Function of Abnormal Status
 Diagnoses the presence or absence of an abnormal condition. By combining High and Low of the input signal and the ST pin, it is possible to grasp overcurrent, heating state, load open state.

Input Signal	ST Signal	Diagnosis Result
L	L	No Abnormality
L	Н	Load Open
Н	L	Over Current or Over Temperature
Н	Н	No Abnormality

Timing Chart




Figure 34. Inductive Load Operation

Timing Chart – continued





Figure 35. Switching Time



Function Description

Over Current Protection Function
 This IC has OCP function. Following is shown that the timing chart of OCP function.




Figure 37. Timing Chart of OCP Function

- ① I_{OUT} is limited at Over Current Limitation Level ($I_{OUT(OCP)}$) = 6 A (Typ) and the V_{OUT} rises when over current is occurred. V_{ST} turns Low.
- ② Current limitation is released when over current is occured. V_{ST} turns High.

Function Description - continued

■ TSD Function

This IC has a built-in TSD function. Following is shown that the timing chart of TSD function.




Figure 38. Timing Chart of TSD Function

- ① The output is turned off when the temperature of the IC reaches Thermal Shutdown Detected Temperature (Tjo) = 175 °C (Typ) or more. V_{ST} turns Low.
- ② The output returns to its normal state when the temperature of the IC becomes Thermal Shutdown Released Temperature (Tjr) = 135 °C (Min) or less. V_{ST} turns High.

Operational Notes

1. Ground Voltage

Ensure that no pins are at a voltage below that of the ground pin at any time, even during transient condition.

2. Ground Wiring Pattern

When using both small-signal and large-current ground traces, the two ground traces should be routed separately but connected to a single ground at the reference point of the application board to avoid fluctuations in the small-signal ground caused by large currents. Also ensure that the ground traces of external components do not cause variations on the ground voltage. The ground lines must be as short and thick as possible to reduce line impedance.

3. Recommended Operating Conditions

The function and operation of the IC are guaranteed within the range specified by the recommended operating conditions. The characteristic values are guaranteed only under the conditions of each item specified by the electrical characteristics.

4. Testing on Application Boards

When testing the IC on an application board, connecting a capacitor directly to a low-impedance output pin may subject the IC to stress. Always discharge capacitors completely after each process or step. The IC's power supply should always be turned off completely before connecting or removing it from the test setup during the inspection process. To prevent damage from static discharge, ground the IC during assembly and use similar precautions during transport and storage.

5. Inter-pin Short and Mounting Errors

Ensure that the direction and position are correct when mounting the IC on the PCB. Incorrect mounting may result in damaging the IC. Avoid nearby pins being shorted to each other especially to ground, power supply and output pin. Inter-pin shorts could be due to many reasons such as metal particles, water droplets (in very humid environment) and unintentional solder bridge deposited in between pins during assembly to name a few.

6. Ceramic Capacitor

When using a ceramic capacitor, determine a capacitance value considering the change of capacitance with temperature and the decrease in nominal capacitance due to DC bias and others.

7. Thermal Shutdown Function (TSD)

This IC has a built-in thermal shutdown function that prevents heat damage to the IC. Normal operation should always be within the IC's maximum junction temperature rating. If however the rating is exceeded for a continued period, the junction temperature (Tj) will rise which will activate the TSD function that will turn OFF power output pins. When the Tj falls below the TSD threshold, the circuits are automatically restored to normal operation.

Note that the TSD function operates in a situation that exceeds the absolute maximum ratings and therefore, under no circumstances, should the TSD function be used in a set design or for any purpose other than protecting the IC from heat damage.


8. Over Current Protection Function (OCP)

This IC incorporates an integrated over current protection function that is activated when the load is shorted. This protection function is effective in preventing damage due to sudden and unexpected incidents. However, the IC should not be used in applications characterized by continuous operation or transitioning of the protection function.


9. Active Clamp Operation

The IC integrates the active clamp function to internally absorb the reverse energy which is generated when the inductive load is turned off. When the active clamp operates, the thermal shutdown function does not work. Please do not exceed active clamp endurance when inductive load is used.

Ordering Information



Marking Diagram



Physical Dimension and Packing Information Package Name SOP-J8 4. 9 ± 0.2 Max 5. 25 (include. BURR) 7 6 5 8 0 ± 0 9 ± 0 . 3 45MIN 0 0. 545 0. 2 ± 0.1 S $375\pm0.$ (UNIT:mm) 0.175 PKG: SOP-J8 Drawing No. EX111-5002 0.42 ± 0.1 1. 27 □ 0. 1 S <Tape and Reel information> Embossed carrier tape Tape 2500pcs Quantity **E2** Direction (The direction is the 1pin of product is at the upper left when you hold reel on the left hand and you pull out the tape on the right hand of feed 0 0 0 0 0 0 0 0 0 0 0 TR TR TR TR E2 TR E2 E2 E2 E2 E2 TR E1 TL Ε1 TL E1 TL Ε1 TL E1 TL E1 Direction of feed Pocket Quadrants Reel

Revision History

Date	Revision	Changes		
26.Feb.2018	001	New Release		
09.Apr.2018	002	P4 Absolute Maximum Ratings Diagnostic output voltage and Diagnostic output current were added.		
25.Jul.2018	003	P9 Electrical Characteristics Slew Rate On and S Slew Rate Off limits were corrected. P13 Figjre 17, 18, 19 and 20 were corrected.		
25.May.2020	004	P22, P23 Function Description Descriptions of Over Current Protection Function and TSD		

Notice

Precaution on using ROHM Products

1. If you intend to use our Products in devices requiring extremely high reliability (such as medical equipment (Note 1), aircraft/spacecraft, nuclear power controllers, etc.) and whose malfunction or failure may cause loss of human life, bodily injury or serious damage to property ("Specific Applications"), please consult with the ROHM sales representative in advance. Unless otherwise agreed in writing by ROHM in advance, ROHM shall not be in any way responsible or liable for any damages, expenses or losses incurred by you or third parties arising from the use of any ROHM's Products for Specific Applications.

(Note1) Medical Equipment Classification of the Specific Applications

JAPAN	USA	EU	CHINA
CLASSIII	ОГУСОШ	CLASS II b	CL A CC TT
CLASSIV	CLASSⅢ	CLASSⅢ	CLASSⅢ

- 2. ROHM designs and manufactures its Products subject to strict quality control system. However, semiconductor products can fail or malfunction at a certain rate. Please be sure to implement, at your own responsibilities, adequate safety measures including but not limited to fail-safe design against the physical injury, damage to any property, which a failure or malfunction of our Products may cause. The following are examples of safety measures:
 - [a] Installation of protection circuits or other protective devices to improve system safety
 - [b] Installation of redundant circuits to reduce the impact of single or multiple circuit failure
- 3. Our Products are not designed under any special or extraordinary environments or conditions, as exemplified below. Accordingly, ROHM shall not be in any way responsible or liable for any damages, expenses or losses arising from the use of any ROHM's Products under any special or extraordinary environments or conditions. If you intend to use our Products under any special or extraordinary environments or conditions (as exemplified below), your independent verification and confirmation of product performance, reliability, etc, prior to use, must be necessary:
 - [a] Use of our Products in any types of liquid, including water, oils, chemicals, and organic solvents
 - [b] Use of our Products outdoors or in places where the Products are exposed to direct sunlight or dust
 - [c] Use of our Products in places where the Products are exposed to sea wind or corrosive gases, including Cl₂, H₂S, NH₃, SO₂, and NO₂
 - [d] Use of our Products in places where the Products are exposed to static electricity or electromagnetic waves
 - [e] Use of our Products in proximity to heat-producing components, plastic cords, or other flammable items
 - [f] Sealing or coating our Products with resin or other coating materials
 - [g] Use of our Products without cleaning residue of flux (Exclude cases where no-clean type fluxes is used. However, recommend sufficiently about the residue.); or Washing our Products by using water or water-soluble cleaning agents for cleaning residue after soldering
 - [h] Use of the Products in places subject to dew condensation
- 4. The Products are not subject to radiation-proof design.
- 5. Please verify and confirm characteristics of the final or mounted products in using the Products.
- 6. In particular, if a transient load (a large amount of load applied in a short period of time, such as pulse, is applied, confirmation of performance characteristics after on-board mounting is strongly recommended. Avoid applying power exceeding normal rated power; exceeding the power rating under steady-state loading condition may negatively affect product performance and reliability.
- 7. De-rate Power Dissipation depending on ambient temperature. When used in sealed area, confirm that it is the use in the range that does not exceed the maximum junction temperature.
- 8. Confirm that operation temperature is within the specified range described in the product specification.
- ROHM shall not be in any way responsible or liable for failure induced under deviant condition from what is defined in this document.

Precaution for Mounting / Circuit board design

- 1. When a highly active halogenous (chlorine, bromine, etc.) flux is used, the residue of flux may negatively affect product performance and reliability.
- 2. In principle, the reflow soldering method must be used on a surface-mount products, the flow soldering method must be used on a through hole mount products. If the flow soldering method is preferred on a surface-mount products, please consult with the ROHM representative in advance.

For details, please refer to ROHM Mounting specification

Notice-PAA-E Rev.004

Downloaded from Arrow.com.

Precautions Regarding Application Examples and External Circuits

- 1. If change is made to the constant of an external circuit, please allow a sufficient margin considering variations of the characteristics of the Products and external components, including transient characteristics, as well as static characteristics.
- 2. You agree that application notes, reference designs, and associated data and information contained in this document are presented only as guidance for Products use. Therefore, in case you use such information, you are solely responsible for it and you must exercise your own independent verification and judgment in the use of such information contained in this document. ROHM shall not be in any way responsible or liable for any damages, expenses or losses incurred by you or third parties arising from the use of such information.

Precaution for Electrostatic

This Product is electrostatic sensitive product, which may be damaged due to electrostatic discharge. Please take proper caution in your manufacturing process and storage so that voltage exceeding the Products maximum rating will not be applied to Products. Please take special care under dry condition (e.g. Grounding of human body / equipment / solder iron, isolation from charged objects, setting of lonizer, friction prevention and temperature / humidity control).

Precaution for Storage / Transportation

- 1. Product performance and soldered connections may deteriorate if the Products are stored in the places where:
 - [a] the Products are exposed to sea winds or corrosive gases, including Cl₂, H₂S, NH₃, SO₂, and NO₂
 - [b] the temperature or humidity exceeds those recommended by ROHM
 - [c] the Products are exposed to direct sunshine or condensation
 - [d] the Products are exposed to high Electrostatic
- 2. Even under ROHM recommended storage condition, solderability of products out of recommended storage time period may be degraded. It is strongly recommended to confirm solderability before using Products of which storage time is exceeding the recommended storage time period.
- 3. Store / transport cartons in the correct direction, which is indicated on a carton with a symbol. Otherwise bent leads may occur due to excessive stress applied when dropping of a carton.
- 4. Use Products within the specified time after opening a humidity barrier bag. Baking is required before using Products of which storage time is exceeding the recommended storage time period.

Precaution for Product Label

A two-dimensional barcode printed on ROHM Products label is for ROHM's internal use only.

Precaution for Disposition

When disposing Products please dispose them properly using an authorized industry waste company.

Precaution for Foreign Exchange and Foreign Trade act

Since concerned goods might be fallen under listed items of export control prescribed by Foreign exchange and Foreign trade act, please consult with ROHM in case of export.

Precaution Regarding Intellectual Property Rights

- 1. All information and data including but not limited to application example contained in this document is for reference only. ROHM does not warrant that foregoing information or data will not infringe any intellectual property rights or any other rights of any third party regarding such information or data.
- 2. ROHM shall not have any obligations where the claims, actions or demands arising from the combination of the Products with other articles such as components, circuits, systems or external equipment (including software).
- 3. No license, expressly or implied, is granted hereby under any intellectual property rights or other rights of ROHM or any third parties with respect to the Products or the information contained in this document. Provided, however, that ROHM will not assert its intellectual property rights or other rights against you or your customers to the extent necessary to manufacture or sell products containing the Products, subject to the terms and conditions herein.

Other Precaution

Downloaded from Arrow.com.

- 1. This document may not be reprinted or reproduced, in whole or in part, without prior written consent of ROHM.
- The Products may not be disassembled, converted, modified, reproduced or otherwise changed without prior written consent of ROHM.
- In no event shall you use in any way whatsoever the Products and the related technical information contained in the Products or this document for any military purposes, including but not limited to, the development of mass-destruction weapons.
- 4. The proper names of companies or products described in this document are trademarks or registered trademarks of ROHM, its affiliated companies or third parties.

Notice-PAA-E Rev.004

General Precaution

- 1. Before you use our Products, you are requested to carefully read this document and fully understand its contents. ROHM shall not be in any way responsible or liable for failure, malfunction or accident arising from the use of any ROHM's Products against warning, caution or note contained in this document.
- 2. All information contained in this document is current as of the issuing date and subject to change without any prior notice. Before purchasing or using ROHM's Products, please confirm the latest information with a ROHM sales representative.
- 3. The information contained in this document is provided on an "as is" basis and ROHM does not warrant that all information contained in this document is accurate and/or error-free. ROHM shall not be in any way responsible or liable for any damages, expenses or losses incurred by you or third parties resulting from inaccuracy or errors of or concerning such information.