SP	FC	IFI	CAT	NS.
J				110

CUSTOMER . TEMP1

SAMPLE CODE . SG24064WRM-EGAI04Q

MASS PRODUCTION CODE . PG24064WRM-EGAI04Q

SAMPLE VERSION . 02

SPECIFICATIONS EDITION . 002

DRAWING NO. (Ver.) : HLMD-PG24064WRM-EGAI04Q (Ver:001)

PACKAGING NO. (Ver.) : HPKG-PG24064WRM-EGAI04Q (Ver:001)

# **Customer Approved**

Date:

Approved	Checked	Designer
王剛,張慶源	詹漢華	楊興華,魏水超,周自立 2008.12.24 HK RD APR

Preliminary specification for design input

Specification for sample approval

#### POWERTIP TECH. CORP.

**Headquarters:** No.8, 6<sup>th</sup> Road, Taichung Industrial Park,

Taichung, Taiwan

TEL: 886-4-2355-8168

E-mail: sales@powertip.com.tw

台中市 407 工業區六路 8 號

FAX: 886-4-2355-8166

Http://www.powertip.com.tw



# **RECORDS OF REVISION**

Date (mm / dd / yyyy)	Ver.	Edi.	Description	Page	Design by
5/27/2008	01	001	The sample has changed the IC, which was based on the Powertip's MASS  PRODUCTION: PG24064WRM-ETIY8Q		張恒
12/23/2008	02	002	The sample has changed the B/L base on the previous sample		楊興華

Total: 25 page



### **Contents**

#### 1. SPECIFICATIONS

- 1.1 Features
- 1.2 Mechanical Specifications
- 1.3 Absolute Maximum Ratings
- 1.4 DC Electrical Characteristics
- 1.5 Optical Characteristics
- 1.6 Backlight Characteristics

#### 2. MODULE STRUCTURE

- 2.1 Counter Drawing
- 2.2 Interface Pin Description
- 2.3 Timing Characteristics
- 2.4 Display command
- 2.5 JUMPER

# 3. QUALITY ASSURANCE SYSTEM

- 3.1 Quality Assurance Flow Chart
- 3.2 Inspection Specification

## 4. RELIABILITY TEST

4.1 Reliability Test Condition

# 5. PRECAUTION RELATING PRODUCT HANDLING

- 5.1 Safety
- 5.2 Handling
- 5.3 Storage
- **5.4** Terms of Warranty

**Appendix: 1. LCM Drawing** 

2. Packing Specification



# 1. SPECIFICATIONS

### 1.1 Features

Item	Standard Value
Display Type	240*64Characters
LCD Type	STN Blue Positive Transmissive Extended Temp.
Driver Condition	LCD Module: 1/64 Duty, 1/9 Bias
Viewing Direction	6 O'clock
Backlight	White LED B/L
Weight	173 g
Interface	8 bit parallel interface
Other(controller / driver IC)	SAP1024
	THIS PRODUCT CONFORMS THE ROHS OF PTC
ROHS	Detail information please refer web side :
	http://www.powertip.com.tw/news/LatestNews.asp

1.2 Mechanical Specifications

Item	Standard Value	Unit
Outline Dimension	180.0 (L) *65.0 (w) * 14.8(H)(Max)	mm
Viewing Area	132.6.0(L) * 39.0(w)	mm
Active Area	127.16(L) * 33.88 (w)	mm
Dot Size	0.49 (L) * 0.49(w)	mm
Dot Pitch	0.53 (L) * 0.53 (w)	mm

Note: For detailed information please refer to LCM drawing

# 1.3 Absolute Maximum Ratings

Item	Symbol	Condition	Min.	Max.	Unit
Power Supply Voltage	$V_{DD}$	1	-0.3	7.0	V
Input Voltage	V <sub>IN</sub>	_	-0.3	V <sub>DD</sub> +0.3	V
Operating Temperature	T <sub>OP</sub>	_	-20	70	$^{\circ}\!\mathbb{C}$
Storage Temperature	$T_{ST}$	_	-30	80	$^{\circ}\!\mathbb{C}$
Storage Humidity	$H_D$	Ta < 60 °C	-	90	%RH




### 1.4 DC Electrical Characteristics

 $V_{DD} = 5.0 \text{ V} \pm 10\%$ ,  $V_{SS} = 0\text{V}$ ,  $Ta = 25^{\circ}\text{C}$ 

Item	Symbol	Condition	Min.	Тур.	Max.	Unit
Logic Supply Voltage	$V_{dd}$	-	4.5	5.0	5.5	V
"H" Input Voltage	$V_{\mathrm{IH}}$	-	V <sub>DD-0.2</sub>	-	V <sub>DD</sub>	V
"L" Input Voltage	$ m V_{IL}$	-	0	-	0.8	V
"H" Output Voltage	$V_{\mathrm{OH}}$	-	V <sub>DD-0.3</sub>	1	V <sub>DD</sub>	V
"L" Output Voltage	$V_{ m OL}$	-	0	-	0.3	V
	Ţ	V <sub>DD</sub> =5.0V;V <sub>OP</sub> =12.7V; Pattern= Full display	-	16.8	-	
Supply Current	$ m I_{dd}$	V <sub>DD</sub> =5.0V;V <sub>OP</sub> =12.7V; Pattern= Horizontal line*1	-	17.0	30	mA
		<b>-20</b> ℃	12.7	12.9	13.1	
LCM Driver Voltage	ver Voltage V <sub>OP</sub> *2	25℃	12.5	12.7	12.9	V
		70℃	12.3	12.5	12.7	

NOTE: \*1 The Maximum current display;

\*2 The VOP test point is VDD-VO.





# 1.5 Optical Characteristics


LCD Panel: 1/64Duty · 1/9Bias ·  $V_{LCD} = 12.7$ V · Ta = 25°C

Item		Symbol	Conditions	Min.	Тур.	Max.	Unit	Reference
Response Time	Rise	tr		-	200	-	ms	Note2
Response Time	Fall	tf		-	150	-	1115	Note2
	Тор	$\Theta Y +$	C≥2.0,	-	- (	40		
Viewing angle	Bottom	ΘΥ-	Ø = 270°	-	-	40	Dag	Notes 1
range	Left	ΘX-		-		45	Deg.	Notes 1
	Right	ΘX+		-	(	45		
Contrast Rat	io	C	$\theta = 0^{\circ},$ $\emptyset = 270^{\circ}$	2.0	4.2	-	-	Note 3
Average Bright (with LCD)		IV		60	72	-	cd/m <sup>2</sup>	
CIE Color Coord	dinate	X		0.141	0.171	0.201	nm	Note 4
(With LCD)*2		y		0.064	0.094	0.124	nm	
Uniformity '	*1	△B		70	-	_	%	

#### Note 4:


- $1 : \triangle B = B(min) / B(max) * 100\%$
- 2 : Measurement Condition for Optical Characteristics:
  - a : Environment:  $25^{\circ}$ C  $\pm 5^{\circ}$ C /  $60\pm 20^{\circ}$ R.H , no wind , dark room below 10 Lux at typical lamp current and typical operating frequency.
  - b: Measurement Distance:  $500 \pm 50 \text{ mm}$ ,  $(\theta = 0^{\circ})$
  - c: Equipment: TOPCON BM-7 fast, (field 1°), after 10 minutes operation.
  - d: The uncertainty of the C.I.E coordinate measurement  $\pm 0.01$ , Average Brightness  $\pm 4\%$






Colorimeter=BM-7 fast












#### Electrical characteristics-2

※2 Drive waveform


Vop: Drive voltage fF: Frame frequency 1/B: Bias fD: Drive frequency

N: Duty

#### (1) Selected waveform



#### (2) Non- Selected wave form




#### Note:

Frame frequency is defined as follows: Common side supply voltage peak - to - peak /2 = 1 period








Active voltage range

	Vth1	Vth2
View direction	10°	40 °
Drive waveform	(Selected waveform)	(No selected waveform)
Transmittance	50%	73%

**※**1 Contrast ratio

= (Brightness in OFF state) / (Brightness in ON state)

Outline of Electro-Optical Characteristics Measuring System



SG24064WRM-EGAI04Q Page10 SAMPLE Ver.02 SPEC Edi.002



# 1.6 Backlight Characteristics


LCD Module with LED Backlight

**Maximum Ratings** 

Item	Symbol	Conditions	Min.	Max.	Unit
Forward Current	IF	Ta =25°C	-	90	mA
Reverse Voltage	VR	Ta =25°C	- 🔥	3.0	V
Reverse Current	IR	VR=3.0V	- ^	0.01	mA
Power Dissipation	PD	Ta =25°C	-	-	W

Electrical / Optical Characteristics

Item	Symbol	Conditions	Min.	Тур.	Max.	Unit
Forward Voltage	VF			3.6	4.2	V
Average Brightness (without LCD)	IV	IF= 90 mA	200	300	-	cd/m <sup>2</sup>
CIE Color Coordinate	X	IF= 90 mA	0.264	-	0.296	
(Without LCD)	Y	11'- 90 IIIA	0.248	-	0.305	•
Color			white			






# 2. MODULE STRUCTURE

# 2.1 Counter Drawing

### 2.1.1 LCM Mechanical Diagram

\* See Appendix

### 2.1.2 Block Diagram






# 2.2 Interface Pin Description

Pin No.	Symbol	Function
1	FG	Frame ground (connected to metal bezel )
2	$V_{ m SS}$	Power Supply (Vss=0)
3	$V_{ m DD}$	Power Supply (V <sub>DD</sub> >V <sub>SS</sub> )
4	$V_{O}$	Operating voltage for LCD
5	WR	Data write (write data to the module at "L")
6	RD	Data read (read data from the module at "L")
7	CE	Chip enable for the module (active at "L")
8	C/ D	$\overline{WR}$ ="L";C/ $\overline{D}$ = "H" :command write,C/ $\overline{D}$ ="L":data write $\overline{RD}$ ="L";C/ $\overline{D}$ = "H" :command read, C/ $\overline{D}$ ="L":data read
9	$ m V_{EE}$	Negative voltage output
10	RESET	Controller reset (module reset)
11~18	DB0	Data bus (DB0=LSB)
12	DB1	Data bus
13	DB2	Data bus
14	DB3	Data bus
15	DB4	Data bus
16	DB5	Data bus
17	DB6	Data bus
18	DB7	Data bus (DB7=MSB)
19	FS	Font select :connect to $V_{DD}$ : 6*8 Dots font connect to $V_{SS}$ : 8*8 Dots font
20	N/A	Not connection




Contrast Adjust





# 2.3 Timing Characteristics

# **Bus Timing**



 $V_{DD}$  =5.0V±0.5V,  $V_{SS}$  =0V, Ta=25  $^{\circ}$ C

symbol	parameter	MIN.	MAX.	test conditions	Unit
tcps	C/D set-up time	100			ns
t <sub>CDH</sub>	C/D hold time	10			ns
t <sub>RD</sub> , t <sub>WR</sub>	RD, WR pulse width	80			ns
t <sub>AS</sub>	Address set-up time	0			ns
t <sub>AH</sub>	Address hold time	0			ns
t <sub>DS</sub>	Data set-up time	80			ns
t <sub>DH</sub>	Data hold time	40			ns
tacc	Access time		150		ns
tон	Output hold time	10	50		ns



# 2.4 Display command

Commands and Registers.

Register Setting	COMMAND	CODE	OPERAND 1	OPERAND 2	FUNCTION
Setting	Danistan	0010 0001	X address	Y address	Set cursor pointer
Mode   Set   Set		0010 0010	Data	00H	Set offset register
Set Control   Word	Cotting	0010 0100	Low address	High address	Set address pointer
Word		0100 0000	Low address	High address	Set text home address
	Set Control	0100 0001	Columns	00H	Set text area
Mode Set	Word	0100 0010	Low address	High address	Set graphic home address
Mode Set		0100 0011	Columns	00H	Set graphic area
Mode Set		1000 x000			OR mode
Mode Set		1000 x001			EXOR mode
1000 x100	Made Cet	1000 x011			AND mode
1000 1xxx	Mode Set	1000 x100			Text Attribute mode
Display mode		1000 0xxx			Internal CG ROM mode
Display mode		1000 1xxx			External CG RAM mode
Display mode   1001 xx11		1001 0000			Display OFF.
1001 01xx		1001 xx10			Cursor ON, blink OFF.
1001 101xx   1001 101x   1010 0000   Selec one-line cursor.   1010 0000   Select two-line cursor.   1010 0010   Select four-line cursor.   1010 0010   Select four-line cursor.   1010 0100   Select four-line cursor.   1010 0100   Select six-line cursor.   1010 0101   Select six-line cursor.   1010 0110   Select six-line cursor.   1010 0111   Select seven-line cursor.   1010 0110   Select seven-line cursor.   1011 0011   Select pata Auto Write   1011 0000   Select Data Auto Write   1011 0001   Select Data Auto Write   1011 0001   Select Data Auto Read   Reset Auto Read/Write   1011 0000   Data   Data Write and increment Address Pointer   1100 0001   Data Write and increment Address Pointer   1100 0010   Data   Data Write and decrement Address Pointer   1100 0101   Data Read and decrement Address Pointer   1100 0101   Data Read and decrement Address Pointer   1100 0101   Data Read and Keep Address Pointer   1100 0101   Data Read and Keep Address Pointer   Data Read and Keep Addre	<u>.</u>	1001 xx11			Cursor ON, blink ON.
1001 11xx	Display mode	1001 01xx			Text ON, graphic OFF.
1001 11xx		1001 10xx			Text OFF, graphic ON.
1010 0000		1001 11xx			
1010 0001		1010 0000			
Data Auto Read/Write   Tourism					Select two-line cursor.
Pattern   Select 1010 0011   Select five-line cursor.		1010 0010			Select three-line cursor.
1010 0100   Select five-line cursor.   Select six-line cursor.   Select six-line cursor.   Select six-line cursor.   Select six-line cursor.   Select seven-line cursor.   Select eight-line cursor.   Select eight-line cursor.   Select Data Auto Write   Select Data Auto Write   Select Data Auto Write   Select Data Auto Read   Select Data Au		1010 0011			Select four-line cursor.
1010 0101   Select six-line cursor.   Select six-line cursor.   Select seven-line cursor.   Select seven-line cursor.   1010 0111   Select eight-line cursor.   Select path Auto Read		1010 0100			Select five-line cursor.
Data Auto Read/Write	Select	1010 0101			
Data Auto Read/Write		1010 0110			Selec seven-line cursor.
Data Auto Read/Write		1010 0111			Select eight-line cursor.
Data Auto Read/Write					-
COMMAND					Select Data Auto Read
1100 0000   Data   Data Write and increment Address Pointer	Read/vvrite	1011 0010			Reset Auto Read/Write
1100 0000   Data   Data Write and increment Address Pointer	COMMAND	CODE	OPERAND 1	OPERAND 2	FUNCTION
Data Read and increment Address Pointer	COMMINATE			OI EIGHD 2	
Data Read and decrement Address Pointer			Data		
Data Read and decrement Address Pointer	Data READ /	1100 0010	Data		Data Write and decrement Address Pointer.
1100 0101   Data Read and Keep Address Pointer		1100 0011			
Screen Peek   1110 0000   Screen peek		1100 0100	Data		Data Write and Keep Address Pointer
Screen Copy		1100 0101			Data Read and Keep Address Pointer
Bit Reset  1111 0xxxx  Bit Reset  1111 1xxxx  Bit Set  1111 x000  Bit 0  1111 x010  Bit 1  1111 x010  Bit 2  1111 x011  Bit 3  1111 x100  Bit 4  1111 x101  Bit 5  1111 x110  Bit 6	Screen Peek	1110 0000			Screen peek
Bit Set/Reset    1111   1xxxx	Screen Copy	1110 1000			Screen copy
Bit Set/Reset  Bit Set/Reset  Bit Set/Reset  Bit 1  1111 x000  Bit 1  1111 x010  Bit 2  1111 x011  Bit 3  1111 x100  Bit 4  1111 x101  Bit 5  1111 x110  Bit 6					
Bit Set/Reset    1111 x001   Bit 1					
Bit Set/Reset 1111 x010 Bit 2 1111 x011 Bit 3 1111 x100 Bit 4 1111 x101 Bit 5 1111 x110 Bit 6					
Bit Set/Reset 1111 x011 Bit 3 1111 x100 Bit 4 1111 x101 Bit 5 1111 x110 Bit 6					
1111 x100 Bit 4 1111 x101 Bit 5 1111 x110 Bit 6	Bit Set/Reset				
1111 x101 Bit 5 1111 x110 Bit 6					
1111 x110 Bit 6					
1111 x111   Bit 7		1111 ×111			Bit 7

# 2.5 JUMPER


JEA/JEK/JP2(2.3)/JA2/JF1/JR/JM5/JF4: SHORT;

OTHERS: OPEN




# 3. QUALITY ASSURANCE SYSTEM

# 3.1 Quality Assurance Flow Chart









# 3.2 Inspection Specification

- ◆Scope: The document shall be applied to LCD Module for Monotype and Color STN (Ver. 03).
- ◆Inspection Standard : MIL-STD-105E Table Normal Inspection Single Sampling Level Ⅱ.
- ◆Equipment : Gauge · MIL-STD · Powertip Tester · Sample
- ◆Defect Level: Major Defect AQL: 0.4; Minor Defect: AQL: 1.5.
- ◆OUT Going Defect Level: Sampling.
- ◆Manner of appearance test :
  - (1). The test be under 20W×2 fluorescent light 'and distance of view must be at 30 cm.
  - (2). Standard of inspection: (Unit: mm)
  - (3). The test direction is base on about around 45° of vertical line. (Fig. 1)
  - (4). Definition of area. (Fig. 2)




Fig.1




Fig. 2 A area: viewing area

#### **◆** Specification:

NO	Item	Criterion	level
		1, 1 The part number is inconsistent with work order of Production.	Major
01	Product condition	1. 2 Mixed production types.	Major
		1. 3 Assembled in inverse direction.	Major
02	Quantity	2. 1 The quantity is inconsistent with work order of production.	Major
03	Outline dimension	3.1 Product dimension and structure must conform to Structure diagram.	Major
		4. 1 Missing line character and icon.	Major
04	Electrical Testing	4. 2 No function or no display.	Major
		4, 3 Output data is error.	Major
		4. 4 LCD viewing angle defect.	Major
		4. 5 Current consumption exceeds product specifications.	Major



## ◆Specification For Monotype and Color STN:

(Yer. 03)

<b>♥</b> Spe	cification For Mone	otype and Color STN:				(Yer. 03)	
NO	Item	Criterion		level			
Black or white dot · scratch · contamination		5. 1 Round type: 5. 1. 1 display only: • White and black spots on 4 white or black spots p • Densely spaced: NO mon	resent.				
		5. 1. 2 Non-display :					
	Daniel ton	Dimension		Acceptance (C	)'ty)	Minor	
	Round type	(diameter : Φ)		A area	B area		
	<b>⇔</b> l√ I⊀⊥	Φ ≤ <b>0</b> . 10	Acce	ept no dense			
05	Y	$0.10 < \Phi \leq 0.20$		3			
บอ	<del>-</del>	$0.20 < \Phi \leq 0.30$		2	Ignore		
	$\Phi = (x+y)/2$	Total quantity		4			
		5. 1. 3 Line type:					
	T : 4	Dimension		Acceptance (Q'ty)			
	Line type	Length (L) Width (W	)	A area	B area		
	_ /¥w	W ≦	0.03	Accept no dense	•		
	→ L +	→ L +	$ \begin{array}{c cccc} L \leq 3.0 & 0.03 < W \leq \\ \hline L \leq 2.5 & 0.05 < W \leq 0 \\ \end{array} $		4	Ignore	
		W >(		As roo	und type		
		Dimension		Acceptance	T		
		(diameter : Φ)	A area		B area		
		$\Phi \leq 0.20$	Accept no dense				
06	Polarizer	$0.20 < \Phi \leq 0.50$		3	]	Minor	
	Bubble	$0.50 < \Phi \le 1.00$		2	Ignore		
		Φ > 1.00		0			
		Total quantity		4			
			•				



glass  Y  [NG]  [OK]  X  Y  Z $\leq$ a  Crack can't enter viewing area  Crack can't exceed the 1/2 t $\leq$ 7 $\leq$ 2 t	♦Specification For Monotype and Color STN: (Ver. 03					
X: The length of crack Z: The thickness of crack X: The thickness of crack T: The thickness of glass X: The width of crack. W: terminal length a: LCD side length  7. 1 General glass chip: 7. 1. 1 Chip on panel surface and crack between panels:  SP  Y  Y  Y  Seal width  X  Y  Z  Crack can't enter viewing area  Crack can't exceed the 1/2 t ∈ 7 ≤ 2 t	NO	Item	Criterion			
7. 1. 1 Chip on panel surface and crack between panels:  The crack of glass  SP  Y  Seal width  X  Y  Z  Crack can't enter viewing area  Crack can't exceed the 1/2 t ∈ 7 ≤ 2 t			X: The length of crack Z: The thickness of crack W: terminal length			
The crack of glass  SP  SP  SP  [NG]  [OK] $X$ $Y$ Seal width $Z$ $X$ $Y$ $Z$ $Z$ $Z$ $Z$ $Z$ $Z$ $Z$						
≤ a Crack can't enter viewing area ≤1/2 t  Crack can't exceed the 1/2 t < 7 < 2 t	07		SP SP [NG]	Minor		
Crack can't exceed the			Crack can't enter			
half of SP width.			Conditional Association			



◆Specification For Monotype and Color STN: (Ver. 03)

NO	Item	Criterion				
		Symbols:  X: The length of crack Z: The thickness of crack t: The thickness of glass  7. 1. 2 Corner crack:				
		X Y Z  Crack can't enter Z < 1/9 t				
		$\leq 1/5$ a Crack can't enter viewing area $Z \leq 1/2$ t $\leq 1/5$ a Crack can't exceed the half of SP width. $1/2$ t < Z ≤ 2 t				
07	The crack of		Minor			
	glass	7.2 Protrusion over terminal:				
		7.2.1 Chip on electrode pad:				
		X X Z X Z Z				
	W					
		X Y Z				
		Front ≤ a ≤ 1/2 W ≤ t				
		Back Neglect				



◆Specification For Monotype and Color STN: (Ver. 03)

NO	Item	Criterion	Level
		Symbols:  X: The length of crack Z: The thickness of crack t: The thickness of glass  X: The width of crack W: terminal length a: LCD side length	
		7. 2. 2 Non-conductive portion:	
07	The crack of glass	X Y Z  ≤1/3 a ≤W ≤t  O If the chipped area touches the ITO terminal, over 2/3 of the ITO must remain and be inspected according to electrode terminal specifications.  7. 2. 3 Glass remain:	Minor
		1. 2. 3 Glass remain: $X$ $Y$	



◆Specification For Monotype and Color STN: (Ver. 03)

NO	Item	Criterion	Level
		8. 1 Backlight can't work normally.	Major
08	Backlight elements	8. 2 Backlight doesn't light or color is wrong.	Major
		8. 3 Illumination source flickers when lit.	Major
		9. 1 Pin type must match type in specification sheet.	Major
		9. 2 No short circuits in components on PCB or FPC.	Major
09	General appearance	9. 3 Product packaging must the same as specified on packaging specification sheet.	Minor
		9. 4 The folding and peeled off in polarizer are not acceptable.	Minor
		9. 5 The PCB or FPC between B/L assembled distance (PCB or FPC) is $\leq 1.5$ mm.	Minor



# 4. RELIABILITY TEST

4.1 Reliability Test Condition

	Reliability Test Condition				
NO.	TEST ITEM	TEST CONDITION			
1	High Temperature Storage Test	Keep in 80 ±2°C 96 hrs			
		Surrounding temperature, then storage at normal condition 4hrs			
2	Low Temperature Storage Test	Keep in $-30 \pm 2^{\circ}$ C 96 hrs			
		Surrounding temperature, then storage			
		Keep in $+60^{\circ}$ C/90%RH duration for 9			
		Surrounding temperature, then storage at normal condition 4hrs			
3	High Humidity Storage	(Excluding the polarizer)			
	Tright Humaity Storage	Air Discharge:	Contact Discharge:		
		Apply 2 KV with 5 times	Apply 250V with 5 times		
		Discharge for each polarity +/-  1. Temperature Ambient: 15°C ~35°C	discharge for each polarity +/-		
		2. Humidity relative: 30% ~ 60%			
1	ESD Togt		7d):150nF+10%		
4 ESD Test 3. Energy Storage Capacitance(Cs+Cd):150pF± 4. Discharge Resistance(Rd):330 Ω±10%					
		<ul><li>5. Discharge, mode of operation:</li></ul>	1070		
		Single Discharge (time between succe	essive discharges at least 1 s)		
		(Tolerance If the output voltage indica	,		
		$-20^{\circ}\text{C} \rightarrow 25^{\circ}\text{C} \rightarrow 70^{\circ}\text{C}$			
_		(30mins) (5mins) (30	Omins) (5mins)		
5	Temperature Cycling Test	10 Cycle	<del></del>		
		Surrounding temperature, then storage			
		1. Sine wave 10~55HZ frequency (			
6	Vibration Test (Packaged)		·		
		<ul><li>2. The amplitude of vibration :1.5 mg</li><li>3. Each direction (XYZ) duration fo</li></ul>			
			Drop Height (cm)		
		0 ~ 45.4	122		
		45.4 ~ 90.8	76		
7	Drop Test (Packaged)	90.8 ~ 454	61		
		Over 454	46		
		Drop direction : **3 comer /	1 edges /6 sides etch 1times		
		210p shrotten (/i/c tellion / i dages / o blade even fullion			



# 5. PRECAUTION RELATING PRODUCT HANDLING

#### **5.1 SAFETY**

- 5.1.1 If the LCD panel breaks, be careful not to get the liquid crystal to touch your skin.
- 5.1.2 If the liquid crystal touches your skin or clothes, please wash it off immediately by using soap and water.

### **5.2 HANDLING**

- 5.2.1 Avoid any strong mechanical shock which can break the glass.
- 5.2.2 Avoid static electricity which can damage the CMOS LSI—When working with the module, be sure to ground your body and any electrical equipment you may be using.
- 5.2.3 Do not remove the panel or frame from the module.
- 5.2.4 The polarizing plate of the display is very fragile. So, please handle it very carefully, do not touch, push or rub the exposed polarizing with anything harder than an HB pencil lead (glass, tweezers, etc.)
- 5.2.5 Do not wipe the polarizing plate with a dry cloth, as it may easily scratch the surface of plate.
- 5.2.6 Do not touch the display area with bare hands, this will stain the display area.
- 5.2.7 Do not use ketonics solvent & aromatic solvent. Use with a soft cloth soaked with a cleaning naphtha solvent.
- 5.2.8 To control temperature and time of soldering is 320±10°C and 3-5 sec.
- 5.2.9 To avoid liquid (include organic solvent) stained on LCM.

### **5.3 STORAGE**

- 5.3.1 Store the panel or module in a dark place where the temperature is  $25^{\circ}\text{C} \pm 5^{\circ}\text{C}$  and the humidity is below 65% RH.
- 5.3.2 Do not place the module near organics solvents or corrosive gases.
- 5.3.3 Do not crush, shake, or jolt the module.


### **5.4 TERMS OF WARRANTY**

5.4.1 Applicable warrant period

The period is within thirteen months since the date of shipping out under normal using and storage conditions.

5.4.2 Unaccepted responsibility

This product has been manufactured to your company's specification as a part for use in your company's general electronic products. It is guaranteed to perform according to delivery specifications. For any other use apart from general electronic equipment, we cannot take responsibility if the product is used in nuclear power control equipment, aerospace equipment, fire and security systems or any other applications in which there is a direct risk to human life and where extremely high levels of reliability are required.



Approve Check Contact Ver.001 LCM包裝規格書 Tang yunxlan Cal zhichuan **∐** zhong LCM Packaging Specifications Documents NO. HPKG-PG24064WRM-EGAI04Q Zhang heng 1.包裝材料規格表 (Packaging Material): (per carton) 1Pcs Weight No. Item Dimensions (mm) Quantity Total Weight 1 PG24064WRM-EGAI04Q 0.174 104 18.096 成品(1) (LCM) 180.0\*65.0\*14.8 靜電袋 (2)BAG 2 BAG250100ARABA 0.0024 104 0.2496 250\*100\*0.05 3 16 0.0464 氣泡墊(3)BAG BAG290240BRBBA 240\*290\*5 0.0029 4 0.011 104 1.144 刀卡A2(4)BX BX29500072BZBA 295\*72\*3 5 0.32 刀卡B2(5)BX 0.01 32 BX24500072BZBA 245\*72\*3 6 C2内盒(6)Product Box BX31025580AABA 310\*255\*86 8 1.768 0.221 7 BX52532536CCBA 外紙箱(7)Carton 525\*325 \*360 1.092 1 1.092 8 9 - 整箱總重量 (Total LCD Weight in carton ): 22.72 Kg±10% 3.單箱數量規格表 (Packaging Specifications and Quantity): (1)Quantity Of Spacer: A2刀卡\*13, B2刀卡\*4 (2)Total LCM quantity in carton: quantity per box x no. of boxes 13 8 104 (3) 氣泡墊 Foam Rubber Cushion (2)靜電袋+(1)LCM Antistatic Bag+LCM (5) B2刀卡 **B2** Partition (4) A2刀卡 A2 Partition (3) 氣泡墊 Foam Rubber Cushion ſĻ (7)外紙箱 Carton (6)C2內盒 Product Box 事 項 (REMARK) 記 1. Label Specifications: MODEL: LOT NO: 前七后六.最后一欄面朝里放 OUANTITY: 置,其余面朝外. CHECK:

POWERTIP TECH, CORP.