



Overview

Presentation	Factory assembled and tested Power Distribution Modules include circuit breaker, power cord, power connection, and circuit monitoring. Auto-detection of modules by the Modular PDU minimizes installation time.
Lead time	Usually Ships within 3 Weeks

General

Provided equipment	Installation guide
--------------------	--------------------

Physical

Depth	40.6 cm
Height	12.7 cm
Net weight	5.73 kg
Width	44.5 cm

Input

Network frequency	60 Hz
Permissible voltage	200...240 V
Max line current	60 A
Input voltage	208 V 3 phases

Output

Max current draw	60 A
Number of power socket outlets	1 IEC 60309 60 A 3P + PE
Output voltage	208 V 3 phases

Conformance

Product certifications	UL listed
------------------------	-----------

Disclaimer: This documentation is not intended as a substitute for and is not to be used for determining suitability or reliability of these products for specific user applications

Packing Units

Package 1 Weight	6.27 kg
Package 1 Height	12.7 cm
Package 1 width	44.5 cm
Package 1 Length	40.6 cm

Offer Sustainability

REACH Regulation	REACH Declaration
EU RoHS Directive	Under investigation
Mercury free	Yes
RoHS exemption information	Yes
Environmental Disclosure	Product Environmental Profile
Circularity Profile	End of Life Information

Contractual warranty

Warranty	1 year repair or replace
----------	--------------------------